

105359565

POLK COUNTY CORNER RESTORATION FORM

SECTION 9 TOWNSHIP 10 S RANGE 5 W W.M. BLM ID 359565

DLC _____ CORNER County Line Monument

DATE 9/22/2011 CORNER RESTORATION FIELD BOOK 200-12 PAGE 20

PREVIOUS RENEWALS / SURVEYS, ETC.

CS 15402; Benton County Survey 134 (10157)

- _____ CONDITION REPORT
- X RENEWED
- _____ UNRECORDED
- _____ SURVEYED IN

MONUMENT AND ACCESSORIES FOUND (CONDITION AND SOURCE)

I found a 3/4" X 24" iron pipe down 12" that was cited as being on the County Line by BCS 134 (10157). A typical County Line concrete guard post is 1.5' west. The post is 10" X 10" at the base, 7" X 7" at the top and 34" high. The post is damaged and is leaning westerly. The as-travelled centerline of Berry Creek Rd. is 29' westerly of the iron pipe.

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I removed said iron pipe and in its place set a 2" X 30" iron pipe with a 2 1/2" brass cap up 4". I layed the old iron pipe beside the new monument.

NEW ACCESSORIES

- 11" fir; S79°E, 18.09'; scribed "BCO BT"; set witness tag
- 12" fir; S70°W, 70.00'; scribed "BCO BT"; set witness tag
- 8" fir; N76°W, 64.20'; scribed "PCO BT"; set witness tag
- 2" X 30" iron pipe with 2 1/2" brass cap located on the County Line bears N89° 54' 30"E, 102.67' (N89° 56'E, 1.554 Ch= 102.56') CS 134; See RE 11887.
- 3/4" iron pipe on east Right-of-Way of Tampico Rd. bears S30° 59' 04"E, 93.14'



State Plane Coordinate (ORGN 83/96 (2002) in Int'l Feet)
 N= 396749.49 ft
 E= 7473968.97 ft

NOTES


1 -All distances to new bearing trees are measured to nail, magnet and Polk County brass washer at center right, 1' high except as noted otherwise.

The state plane coordinates given for this point are the result of ties made during the survey for county project 1021, point #50.
 See project file for more information.

MONUMENT DETAIL



SKETCH



RESTORATION NO.

11908

REGISTERED PROFESSIONAL LAND SURVEYOR

Eric T Berry
 OREGON
 JANUARY 15 2002
 ERIC T BERRY
 61392

FIRM / AGENCY

Polk County Surveyors Office
 820 S.W. Ash St.
 Dallas, Oregon 97338
 (503) 623-9287

WITNESS Jim Killian, Roger Ray