

105658565

POLK COUNTY CORNER RESTORATION FORM

SECTION 12 TOWNSHIP 10 S RANGE 5 W W.M. BLM ID 658565

DLC _____ CORNER County Line Monument

DATE 4/14/2011 CORNER RESTORATION FIELD BOOK 200-12 PAGE 4

PREVIOUS RENEWALS / SURVEYS, ETC.

CS 2629, 3667, 13143, 13663, 14587, 14661, 15402;
Benton Co. Survey 10157 (134)

 RENEWED

UNRECORDED

SURVEYED IN

MONUMENT AND ACCESSORIES FOUND (CONDITION AND SOURCE)

I found a 2' section of a plow share standing vertically with the top of the plowshare 1' below the ground. The plowshare is cited by BCS 134 as being on the County Line. A fence corner post is 1' southwest. The centerline of a gravel access road is 10' southeast.

MONUMENT SET (PROCEDURES AND DESCRIPTION)

I referenced the high point of the plow share. I then removed the plowshare and at said high point set a 2" X 30" iron pipe with 2 1/2" brass cap up 6". I layed the plow share beside the iron pipe and cap.

NEW ACCESSORIES

-Power Pole #K12L18 1/2 R5: S69°W, 41.71' to a nail and washer 1' up on the left; set witness tag.

I tied to three iron rods and caps set by CS 14661. See the "To Reach" sketch below:

- IRC 1: S37°W, 199.37'; IRC down 4"
- IRC 2: S78°W; 100.60'; IRC down 2"
- IRC 3: N59°W; 162.70'; IRC is flush

- I set a carsonite post 1' north of the monument
- There were no trees available to use as bearing trees.


State Plane Coordinate (ORGN 83/96 (2002) in Int'l Feet)

N= 396175.41 ft
E= 7489878.89 ft

NOTES

The state plane coordinates given for this point are the result of ties made during the survey for county project 1021, point #45.
See project file for more information.

MONUMENT DETAIL




FIRM / AGENCY

Polk County Surveyors Office
820 S.W. Ash St.
Dallas, Oregon 97338
(503) 623-9287

WITNESS Jim Killian, Roger Ray

SKETCH



RESTORATION NO.

11884

REGISTERED
PROFESSIONAL
LAND SURVEYOR


OREGON
JANUARY 15 2002
ERIC T BERRY
61392