

11-7-33

12-7-A

117360100

ESTABLISHED CORNER FOR OREGON STATE BOARD OF FORESTRY

1150

East one-sixteenth corner common to Sections 33 and 4, T11 and 12S, R7W, W.M., Benton County, Oregon.

ESTABLISHED

Set 1 1/2" x 36" galvanized iron pipe with 3" bronze cap marked "OREGON STATE BOARD OF FORESTRY E 1/16 S33 S4 1959 RE2311", 30 inches in ground, and from which a:


25" Fir bears S44°E 63.0 ft.; scribed E 1/16 S4 BT RE2311.

25" Fir bears N10E 31.5 ft.; scribed E 1/16 S33 BT.

Oregon State Board of Forestry metal location poster on 25" Fir N10E.
Set 4 x 4 x 72" white painted Cedar post 1 foot SW of pipe.

Dated July 13, 1959

Established by *G. Skog* under my direction.
G. Skog



Present and witnessed by H. Baughn