


C.S. # 2738

See notes in file

F.B.



RT. 3, BOX 8

RES. PH. 1-5752

LEBANON, OREGON

January 18, 1956

2738

Curtiss Hanson  
Benton County Surveyor  
County Courthouse  
Corvallis, Oregon

Dear Sir:

We have had occasion to locate the NE corner Section 24, T 11 S, R 8 W on the line between Benton and Lincoln counties.

The stone is in place and there are remains of three out of the four original BT's matching the original note bearings and distances.

I scribed new BT's as follows:

32" Fir	N 15 E	51.8 ft.
12" Fir	S 18 W	24.0 ft.
9" Fir	S 86 E	24.0 ft.
6" Fir	N 33 W	8.0 ft.

I ran the mile (chained 5,264.8 ft.) from NW corner 24 to above NE corner 24 with staff compass and set a tie rod in broken glass for approximate N  $\frac{1}{4}$  corner. This rod is about 60 ft. east of old fence corner. No BT's set for  $\frac{1}{4}$  corner as it is not done by transit.

Yours very truly,

*Howard E. Taylor*

Howard E. Taylor  
Registered Professional Engineer

HET:BW